

**BOBCAT COMPANY PRICE PAGES**  
**NA UTILITY WORK MACHINES - TOOLCAT™**



**Please note the following when using Bobcat Price Pages:**

- All prices are shown in U.S. dollars.
- Check DealerNET Pricing Homepage for current Canadian exchange rate.
- To ensure having the correct Part Number for a Dealer Installed Accessory, obtain the model and serial number and check with Dealer Parts Department.
- For current Dealer Installed Accessories pricing, reference BobQuote or Dealer Parts Department.
- Prices and specifications are subject to change without notice.

**THE FOLLOWING UPDATES HAVE BEEN MADE TO THIS DOCUMENT:**

Date	Description of Change
8/18/2021	New 2021 Model Year Release
11/1/2021	Effective Monday, November 1st, 2021 Bobcat Company has adjusted the SLP of powered units
7/1/2022	Effective Monday, July, 1st, 2022 Bobcat Company has adjusted the SLP of powered units
1/1/2023	Bobcat Company has adjusted SLP of powered units and options
7/1/2023	Bobcat Company has adjusted SLP of powered units
1/1/2024	Bobcat Company has adjusted SLP of powered units
7/1/2024	Bobcat Company has adjusted SLP of powered units
1/1/2025	Bobcat Company has adjusted SLP of powered units
12/9/2025	Bobcat Company has adjusted SLP of powered units and options
1/1/2026	Release Of New 2026 Pricing

*\*Certain Specification(s) are based on engineering calculations and are not actual measurements. Specification(s) are provided for comparison purposes only and are subject to change without notice. Specification(s) for your individual Bobcat equipment will vary based on normal variations in design, manufacturing, operating conditions, and other factors.*

## UW56 Utility Work Machine



### Standard Equipment

#### Engine

- 61HP 2.4L Bobcat Engine
- Automatically Activated Glow Plugs

#### Drive System

- Limited Slip Transaxle
- Two-Speed Transmission
- Parking Brake, automatic
- Full-time Four-Wheel Drive
- All-Wheel Steer
- Horsepower Management
- Speed Management

#### Steering & Suspension

- Suspension, 4-wheel independent
- Power Steering with Tilt Steering Wheel

#### Operator Comfort

- Enclosed cab with HVAC
- Front Windshield Wiper
- Adjustable Driver Seat
- Seat Belts, Shoulder Harness
- Beverage Holders
- Cruise Control

#### Front Work Group

- Bob-Tach™ Mounting System
- Auxiliary Hydraulics: Variable Flow with dual direction detent
- Boom Float
- Lift Arm Support

#### Tires

- Tires: 27 x 10.5-15 (8 ply), Lug Tread

#### Electrical

- LED Front Work Lights
- Combo Type A and Type C USB charging port
- Dome Light
- Toolcat Interlock Control System (TICS)™
- 

#### Instrumentation

- 5" Display with Jog Shuttle
- Following are shown in display: Hour meter, Speedometer, Tachometer, Fuel Gauge, Engine Temperature Gauge, Service and Error Codes
- Engine and Hydraulic Monitor with Shutdown

#### Frame & Cargo Box

- Rear Receiver Hitch
- Hydraulic Dump Box
- Cargo Box Support
- Radiator Screen
- Lower Engine Cover

#### Warranty

- Machine Warranty: 12 Months, Unlimited Hours
- Bobcat Engine Warranty: Additional 12 months or total of 2000 hours after initial 12 month warranty

**Roll Over Protective Structure (ROPS) – Meets Requirements of SAE-J1040 & ISO 3471**  
**Falling Object Protective Structure (FOPS) – Meets Requirements of SAE-J1043 & ISO3449, Level I**

## UW56 Utility Work Machine

### Quick Specs

Engine Model.....	2.4L Bobcat Engine
Horsepower .....	61
Engine Fuel/Cooling.....	Diesel/Liquid
Hydraulic Flow-Attachment.....	18.9 GPM
Hydraulic Flow-Attachment/High Flow.....	27.9 GPM
Hydraulic Pressure.....	3000 PSI
Travel Speed (Low).....	0-8 MPH
Travel Speed (High).....	0-17 MPH
Travel Speed (Reverse).....	0-8 MPH
Operating Weight.....	5680 lbs.
Fuel Capacity.....	20 gal.
Dimensions (Length x Width x Height)-27 in. Tires.....	145 in. x 60 in. x 81 in.
Dimensions (Length x Width x Height)- 29 in. Tires.....	145 in. x 64 in. x 82 in.
Ground Clearance – with 27 in. tires.....	8 in.
Ground Clearance – with 29 in. tires.....	9 in.
Cargo Box Specifications.....	
Inside Dimensions (Length x Width x Height).....	56 in. x 51 in. x 10 in.
Bed Height from Ground.....	38 in.
Cargo Box Maximum Load.....	2000 lbs.
Turning Diameter-outside in AWS mode.....	17.5 ft.
Lift Height.....	83 in.
Maximum Reach.....	45 in.
Loader Rated Operating Capacity.....	1500 lbs.
Tow Rating.....	4000 lbs.
Machine Rated Capacity	
(combined weight of load on lift-arm, cargo box load, and operator and passenger).....	2200 lbs.
Total Rated Capacity	
(combined weight of load on lift-arm, cargo box load, operator and passenger, and tow weight).....	4200 lbs.

Part Number	Description	Utility Work Machine	SLP In US \$
M1225	UW56 Utility Work Machine.....		\$ 84,448

UW56			
Utility Work Machine			
Part Number	Description	Factory Installed Options	SLP In US \$

**Individual Options**

M1225-R08-C02	Attachment Control.....	\$	295
M1225-P01-C01	Deluxe Road Package..... Includes back-up alarm, turn signals, flashers, taillights, brake lights, rear view mirror, side mirrors, horn, rear work light, and headlights <i>Allows Work Machine to meet most regulations for driving on local roadways. Check with local DMV to confirm all requirements for off-highway machinery on your local roads. Toolcat machines are not "automobiles" and thus do not need to be licensed to drive on local roads, but usually require lighting and mirrors included in this package.</i>	\$	3,407
M1225-R07-C02	Heavy Duty Battery.....	\$	121
M1225-R03-C02	High Flow Package..... Includes high flow valve, larger auxiliary hoses, and high flow switch in cab; Provides 27.9 GPM for attachment operation; Must also order 7-Pin Attachment Control	\$	2,275
M1225-A01-C04	Interior Trim..... Insulation for left and right-side panels of center console	\$	237
M1225-R14-C03	Power Bob-Tach® Attachment Mounting System.....	\$	1,326
M1225-R15-C02	Radio Option..... Features Aux mini jack for MP-3, Weatherproof design, NOAA Weather Bands, 6 AM & 5 FM presets, Time & Date, Job Clock, Backlit display, 3.5 mm headphone jack, 12volt DC power outlet	\$	622
M1225-R16-C02	Traction Control..... Senses wheel speed variation during limited traction, applies braking to increase torque to wheels in traction, Includes switch in cab for system deactivation	\$	730
M1225-R20-C01	Rearview Camera..... Rearview camera mounted on the back of the cab	\$	413
M1225-A01-C02	Block Heater.....	\$	168

**Tire Options Set of 4 Tires**

*Set of 4 Tires– In Place of Base Equipment*

M1225-R05-C04	29 x 10.5, 10 PR, Trac Tires..... Work Machine Width – 60"	\$	754
M1225-R05-C05	29 x 12.5, 8 PR, Turf Tires..... Work Machine Width – 64"; Includes wide fenders	\$	1,127

<div>UW56</div> <div>Utility Work Machine</div>		
Part Number	Description	SLP In US \$
7269859	<b>Heavy Duty Cold Weather Battery.....</b> This heavy duty battery is designed to provide consistent power at low temperatures. Cold cranking current at 0°F = 1000 Amps Estimated Install Time .5 hours	\$_____
6817260	<b>Rear View Mirror Kit.....</b> Includes mirror, mounting puck, and epoxy to attach to front window Estimated Install Time 1 hour	\$_____
7432514	<b>Side Mirror Kit.....</b> Includes both mirrors and mounting brackets Estimated Install Time 1 hour	\$_____
7328972	<b>Block Heater Kit.....</b> Allows for improved cold weather starting. Estimated Install Time .25 hours	\$_____
7439793	<b>Center Insulation Kit.....</b> Insulation for the left and right panels of the center console. Estimated Install Time .5 hours	\$_____
7439791	<b>Horn Kit.....</b> Make others aware of your presence with this horn kit. Estimated Install Time .75 hours	\$_____
7107773	<b>Hitch Adapter.....</b> Needs Qty 4 - 7416145 (Hex Head Screw) Estimated Install Time .5 hours	\$_____
7439954	<b>Attachment Control Kit, 7-Pin.....</b> Controls 7-Pin Attachments only; Includes 3 switches mounted in center console Estimated Install Time 1 hour	\$_____
7120242	<b>Attachment Control Kit, 14-Pin.....</b> Controls 14-Pin Attachments only Estimated Install Time .5 hours	\$_____
7122379	<b>Remote Rear Hydraulics Kit, 2.5 GPM.....</b> Diverts hydraulic flow from the cargo box hydraulic system to rear poppet-style couplers. The cargo box and the remote rear hydraulics cannot be operated at the same time. Distributes a momentary flow rate of 2.5 GPM. Estimated Install Time 2 hours	\$_____
7441192	<b>Remote Rear Aux Hydraulics Kit, 18 GPM.....</b> Diverts hydraulic flow from the front auxiliary hydraulic system to rear flush face couplers. Front and Rear Auxiliary Hydraulics cannot be operated at the same time. Distributes continuous flow up to 18 GPM Estimated Install Time 6 hours	\$_____

<div>UW56</div> <div>Utility Work Machine</div>		
Part Number	Description	SLP In US \$

7134486	<b>Lower Debris Guard.....</b> Protects engine and fuel tank section under cab from mud and other debris Estimated Install Time 1.25 hours	\$_____
7135575	<b>Step Kit.....</b> Includes one step for installation to right or left side Estimated Install Time 1.5 hours	\$_____
7150926	<b>Rear Window Guard Kit.....</b> Rear window guard provides coverage of the rear window while offering clear visibility. Estimated Install Time .5 hours	\$_____
7187118	<b>Hose Guide Kit.....</b> Guide installed on left side of Bob-Tach to keep attachment hoses away from the front tire Estimated Install Time .5 hours	\$_____
7190022	<b>Box Pocket Kit.....</b> Support brackets for the cargo box to allow for stake posts to assist in securing items. Estimated Install Time .5 hours	\$_____
7199661	<b>Side Screen Kit.....</b> Additional screen to filter air before being pulled into AC condenser Estimated Install Time .5 hours	\$_____
7245066	<b>Air Pre-Cleaner Kit.....</b> Collects larger particles prior to air filter providing longer filter life Estimated Install Time 2 hours	\$_____
7423165	<b>Fire Extinguisher Kit.....</b> Mount and secure a fire extinguisher to your utility work machine Estimated Install Time .5 hours	\$_____
7424195	<b>Beacon Kit.....</b> The Beacon Light increases visibility in traffic or low visibility conditions. Estimated Install Time 1 hour	\$_____
7424783	<b>Strobe Light Kit.....</b> The Strobe Light increases visibility in traffic or low visibility conditions. Estimated Install Time 1 hour	\$_____
7427257	<b>Telematics Bobcat Machine IQ Kit.....</b> Connected Machine Capabilities Estimated Install Time 1.5 hours	\$_____
7432520	<b>Road Light Kit.....</b> Headlights, Taillights and fenders Estimated Install Time 3 hours	\$_____
7432522	<b>Rear Camera Kit, Cab Mounted.....</b> Rear camera mounted on the back of the cab. Includes camera and mounting hardware.	\$_____

Estimated Install Time 1 hour

UW56		
Utility Work Machine		
Part Number	Description	SLP In US \$
7432524	<b>Rear Camera Kit, Frame Mounted</b> ..... Mounts the rear camera on the frame for a view that is optimized to the receiver hitch Estimated Install Time 1 hour	\$_____
7434156	<b>Floorboard Riser Kit</b> ..... Raises floorboard for operator comfort and pedal accessibility Estimated Install Time 1 hour	\$_____
7434733	<b>Backup Alarm Kit</b> ..... The back-up alarm alerts others to your backing vehicle. Estimated Install Time 1 hour	\$_____
7439789	<b>Rear Work Light Kit</b> ..... Alternative to the push button start, this kit allows for a keyed operation solution Estimated Install Time .5 hours	\$_____
7439795	<b>Key Start Kit</b> ..... Increase visibility with the two included LED lights. Estimated Install Time 2 hours	\$_____
7460863	<b>Suspension Seat, Driver Side</b> ..... Suspension Seat Kit for Toolcat™ Work Machines, 7460863 is grey vinyl with an embossed Bobcat head. Equipped with internal suspension with a weight adjust handle, arm rest, seat sliders, seat plate, insulation, hardware, and installation Estimated Install Time 1 hour	\$_____
7439797	<b>Radio Installation Kit</b> ..... Heavy duty multi-function radio with Bluetooth capability Estimated Install Time 1 hour	\$_____
7432516	<b>Fender Kit (Standard)</b> ..... Standard front and rear fender flares for utility work machines Estimated Install Time 1 hour	\$_____
7432518	<b>Fender Kit (Wide)</b> ..... Wide front and rear fender flares for utility work machines Estimated Install Time 1 hour	\$_____
7425595	<b>Snow Tire 29.7 X 7 X 15 - 10 PLY</b> ..... (Reference 15 x 6 6ON5.5 + 2.25 wheel pt#6690640) Estimated Install Time .25 hours	\$_____
7166360	<b>Turf Tire 29 X 12.5 X 15 - 8 PLY</b> ..... (Reference 15 x 10 6ON5.5 + .25 wheel pt#6688857) Estimated Install Time .25 hours	\$_____
6682461	<b>Turf Tire 27 X 10.5 X 15 10 - PLY</b> ..... (Reference 15 x 8 6ON5.5 + 1.25 wheel pt#6688856) Estimated Install Time .25 hours	\$_____

UW56		
Utility Work Machine		
Part Number	Description	SLP In US \$
7023289	<b>Industrial Tire 27 X 10.5 X 15 - 8 PLY.....</b> (Reference 15 x 8 6ON5.5 + 1.25 wheel pt#6688856) Estimated Install Time .25 hours	\$_____
7023288	<b>Industrial Tire 29 X 10.5 X 15 - 10 PLY.....</b> (Reference 15 x 8 6ON5.5 + 1.25 wheel pt#6688856) Estimated Install Time .25 hours	\$_____
7211382	<b>Float Tire 31 X 12 X 16.5 - 10 PLY.....</b> (Reference 16.5 x 9.75 6ON5.5 - .625 wheel pt#6690642) Estimated Install Time .25 hours	\$_____
6690640	<b>Wheel - 15 x 6 6ON5.5 +2.25.....</b> Works with Snow Tire pt#7425595 Estimated Install Time .25 hours	\$_____
6688856	<b>Wheel - 15 x 8 6ON5.5 +1.25.....</b> Works with Industrial Tires pt#'s7023288, 7023289 & Turf Tire pt#6682461 Estimated Install Time .25 hours	\$_____
6688857	<b>Wheel - 15 x 10 6ON5.5 +.25.....</b> Works with Turf Tire pt#7166360 Estimated Install Time .25 hours	\$_____
6690642	<b>Wheel - 16.5 x 9.75 6ON5.5 -.625.....</b> Works with Float Tire pt#7211382 Estimated Install Time .25 hours	\$_____





## UW53 Utility Work Machine



### Standard Equipment

#### Engine

- 61HP 2.4L Bobcat Engine
- Automatically Activated Glow Plugs

#### Drive System

- Limited Slip Transaxle
- Two-Speed Transmission
- Parking Brake, automatic
- Full-time Four-Wheel Drive
- All-Wheel Steer
- Horsepower Management
- Speed Management

#### Steering & Suspension

- Suspension, 4-wheel independent
- Power Steering with Tilt Steering Wheel

#### Operator Comfort

- Enclosed cab with HVAC
- Radio W/Aux Input & Headphone Jack
- Front Windshield Wiper
- Driver Adjustable Vinyl Seats
- Seat Belts, Shoulder Harness
- Beverage Holders
- Cruise Control
- Deluxe Road Package: Backup alarm, turn signals, flashers, tail lights, brake lights, and rear work lights
- Interior Trim

#### Front Work Group

- Power Bob-Tach™ Mounting System
- Auxiliary High Flow Hydraulics: Variable Flow with dual direction detent
- Attachment Control Kit
- Boom Float
- Lift Arm Support

#### Tires

- Tires: 27 x 10.5-15 (8 ply), Lug Tread

#### Electrical

- LED Front Work Lights
- Combo Type A and Type C USB charging port
- Dome Light
- Toolcat Interlock Control System (TICS)™

#### Instrumentation

- 5" Display with Jog Shuttle
- Following are shown in display: Hour meter, Speedometer, Tachometer, Fuel Gauge, Engine Temperature Gauge, Service and Error Codes
- Engine and Hydraulic Monitor with Shutdown

#### Frame & Rear

- Rear Receiver Hitch
- Rear PTO- 540 PTO, PTO Shield, PTO Tachometer
- Rear Remote Package: One set of poppet-style couplers, (for use with implement hydraulics)
- Radiator Screen
- Lower Engine Cover
- Three-Point Hitch Package: Category 1 Three-Point, Depth Position Gauge

#### Warranty

- Machine Warranty: 12 Months, Unlimited Hours
- Bobcat Engine Warranty: Additional 12 months or total of 2000 hours after initial 12 month warranty

**Roll Over Protective Structure (ROPS) – Meets Requirements of SAE-J1040 & ISO 3471**

## UW53 Utility Work Machine

### Quick Specs

Engine Model.....	2.4L Bobcat Engine
Horsepower .....	61
Engine Fuel/Cooling.....	Diesel/Liquid
Hydraulic Flow-Attachment.....	18.9 GPM
Hydraulic Flow-Attachment/High Flow.....	27.9 GPM
Hydraulic Pressure.....	3000 PSI
PTO Horsepower.....	25 HP
PTO RPM.....	540
Travel Speed (Low).....	0-8 MPH
Travel Speed (High).....	0-17 MPH
Travel Speed (Reverse).....	0-8 MPH
Operating Weight.....	5710 lbs.
Fuel Capacity.....	20 gal.
Dimensions (Length x Width x Height)-27 in. Tires.....	154 in. x 60 in. x 81 in.
Dimensions (Length x Width x Height)- 29 in. Tires.....	154 in. x 64 in. x 82 in.
Ground Clearance – with 27 in. tires.....	8 in.
Ground Clearance – with 29 in. tires.....	9 in.
Turning Diameter-outside in AWS mode.....	17.5 ft.
Lift Height.....	83 in.
Maximum Reach.....	45 in.
Loader Rated Operating Capacity.....	1500 lbs.
Three-Point Hitch Lift Capacity at 24 inches behind lift point with loader bucket.....	1775 lbs.
Tow Rating.....	4000 lbs.
Machine Rated Capacity	2200 lbs.
(combined weight of load on lift-arm, three-point, operator and passenger, and storage bins).....	
Total Rated Capacity	4200 lbs.

(combined weight of load on lift-arm, three point, storage bins, operator and passenger, and tow weight)

Part Number	Description	Utility Work Machine	SLP In US \$
-------------	-------------	----------------------	--------------

M1227	UW53 Utility Work Machine.....		\$ 100,665
-------	--------------------------------	--	------------

Part Number	Description	Factory Installed Options	SLP In US \$
-------------	-------------	---------------------------	--------------

M1227-A01-C02	Block Heater.....		\$ 168
---------------	-------------------	--	--------

M1227-R20-C01	Rearview Camera.....		\$ 413
	Rearview camera mounted on the back of the cab		

<div> <div>UW53</div> <div>Utility Work Machine</div> </div>		
Part Number	Description	Factory Installed Options
		SLP In US \$

**Tire Options**

*Set of 4 Tires– In Place of Base Equipment*

M1227-R05-C04	29 x 10.5, 10 PR, Trac Tires..... Work Machine Width – 60"	\$ 754
M1227-R05-C05	29 x 12.5, 8 PR, Turf Tires..... Work Machine Width – 64"; Includes wide fenders	\$ 1,127

Part Number	Description	Dealer Installed Accessories - Order From Parts
		SLP In US \$

7269859	<b>Heavy Duty Cold Weather Battery</b> ..... This heavy duty battery is designed to provide consistent power at low temperatures. Cold cranking current at 0°F = 1000 Amps Estimated Install Time .5 hours	\$_____
6817260	<b>Rear View Mirror Kit</b> ..... Includes mirror, mounting puck, and epoxy to attach to front window Estimated Install Time 1 hour	\$_____
7432514	<b>Side Mirror Kit</b> ..... Includes both mirrors and mounting brackets Estimated Install Time 1 hour	\$_____
7328972	<b>Block Heater Kit</b> ..... Allows for improved cold weather starting. Estimated Install Time .25 hours	\$_____
7439793	<b>Center Insulation Kit</b> ..... Insulation for the left and right panels of the center console. Estimated Install Time .5 hours	\$_____
7439791	<b>Horn Kit</b> ..... Make others aware of your presence with this horn kit. Estimated Install Time .75 hours	\$_____
7439954	<b>Attachment Control Kit, 7-Pin</b> ..... Controls 7-Pin Attachments only; Includes 3 switches mounted in center console Estimated Install Time 1 hour	\$_____
7120242	<b>Attachment Control Kit, 14-Pin</b> ..... Controls 14-Pin Attachments only Estimated Install Time .5 hours	\$_____
7122379	<b>Remote Rear Hydraulics Kit, 2.5 GPM</b> ..... Diverts hydraulic flow from the cargo box hydraulic system to rear poppet-style couplers. The cargo box and the remote rear hydraulics cannot be operated at the same time. Distributes a momentary flow rate of 2.5 GPM. Estimated Install Time 2 hours	\$_____

<div> <div>UW53</div> <div>Utility Work Machine</div> </div>			
Part Number	Description	Dealer Installed Accessories - Order From Parts	SLP In US \$
7441192	<b>Remote Rear Aux Hydraulics Kit, 18 GPM.....</b> Diverts hydraulic flow from the front auxiliary hydraulic system to rear flush face couplers. Front and Rear Auxiliary Hydraulics cannot be operated at the same time. Distributes continuous flow up to 18 GPM Estimated Install Time 6 hours		\$_____
7134486	<b>Lower Debris Guard.....</b> Protects engine and fuel tank section under cab from mud and other debris Estimated Install Time 1.25 hours		\$_____
7135575	<b>Step Kit.....</b> Includes one step for installation to right or left side Estimated Install Time 1.5 hours		\$_____
7187118	<b>Hose Guide Kit.....</b> Guide installed on left side of Bob-Tach to keep attachment hoses away from the front tire Estimated Install Time .5 hours		\$_____
7199661	<b>Side Screen Kit.....</b> Additional screen to filter air before being pulled into AC condenser Estimated Install Time .5 hours		\$_____
7245066	<b>Air Pre-Cleaner Kit.....</b> Collects larger particles prior to air filter providing longer filter life Estimated Install Time 2 hours		\$_____
7423165	<b>Fire Extinguisher Kit.....</b> Mount and secure a fire extinguisher to your utility work machine Estimated Install Time .5 hours		\$_____
7424195	<b>Beacon Kit.....</b> The Beacon Light increases visibility in traffic or low visibility conditions. Estimated Install Time 1 hour		\$_____
7424783	<b>Strobe Light Kit.....</b> The Strobe Light increases visibility in traffic or low visibility conditions. Estimated Install Time 1 hour		\$_____
7427257	<b>Telematics Bobcat Machine IQ Kit.....</b> Connected Machine Capabilities Estimated Install Time 1.5 hours		\$_____
7432520	<b>Road Light Kit.....</b> Headlights, Taillights and fenders Estimated Install Time 3 hours		\$_____
7432522	<b>Rear Camera Kit, Cab Mounted.....</b> Rear camera mounted on the back of the cab. Includes camera and mounting hardware. Estimated Install Time 1 hour		\$_____

UW53 Utility Work Machine		
Part Number	Description	SLP In US \$
7434156	<b>Floorboard Riser Kit.....</b> Raises floorboard for operator comfort and pedal accessibility Estimated Install Time 1 hour	\$_____
7434733	<b>Backup Alarm Kit.....</b> The back-up alarm alerts others to your backing vehicle. Estimated Install Time 1 hour	\$_____
7439789	<b>Rear Work Light Kit</b> Alternative to the push button start, this kit allows for a keyed operation solution Estimated Install Time .5 hours	\$_____
7439795	<b>Key Start Kit.....</b> Increase visibility with the two included LED lights. Estimated Install Time 2 hours	\$_____
7460863	<b>Suspension Seat, Driver Side.....</b> Suspension Seat Kit for Toolcat™ Work Machines, 7460863 is grey vinyl with an embossed Bobcat head. Equipped with internal suspension with a weight adjust handle, arm rest, seat sliders, seat plate, insulation, hardware, and installation Estimated Install Time 1 hour	\$_____
7439797	<b>Radio Installation Kit.....</b> Heavy duty multi-function radio with Bluetooth capability Estimated Install Time 1 hour	\$_____
7432516	<b>Fender Kit (Standard).....</b> Standard front and rear fender flares for utility work machines Estimated Install Time 1 hour	\$_____
7432518	<b>Fender Kit (Wide).....</b> Wide front and rear fender flares for utility work machines Estimated Install Time 1 hour	\$_____
7257423	<b>Rear RH Remote Hydraulic Kit.....</b> Right Rear Poppet Style Hydraulic connectors Estimated Install Time 1 hour	\$_____
7174730	<b>Rear Aux Orifice Kit.....</b> Limits hydraulic flow rate to Includes 1.5, 3.0, 7.0 gpm orifices Estimated Install Time .75 hours	\$_____

UW56		
Utility Work Machine		
Part Number	Description	SLP In US \$
7425595	<b>Snow Tire 29.7 X 7 X 15 - 10 PLY.....</b> (Reference 15 x 6 6ON5.5 + 2.25 wheel pt#6690640) Estimated Install Time .25 hours	\$_____
7166360	<b>Turf Tire 29 X 12.5 X 15 - 8 PLY.....</b> (Reference 15 x 10 6ON5.5 + .25 wheel pt#6688857) Estimated Install Time .25 hours	\$_____
6682461	<b>Turf Tire 27 X 10.5 X 15 10 - PLY.....</b> (Reference 15 x 8 6ON5.5 + 1.25 wheel pt#6688856) Estimated Install Time .25 hours	\$_____
7023289	<b>Industrial Tire 27 X 10.5 X 15 - 8 PLY.....</b> (Reference 15 x 8 6ON5.5 + 1.25 wheel pt#6688856) Estimated Install Time .25 hours	\$_____
7023288	<b>Industrial Tire 29 X 10.5 X 15 - 10 PLY.....</b> (Reference 15 x 8 6ON5.5 + 1.25 wheel pt#6688856) Estimated Install Time .25 hours	\$_____
7211382	<b>Float Tire 31 X 12 X 16.5 - 10 PLY.....</b> (Reference 16.5 x 9.75 6ON5.5 - .625 wheel pt#6690642) Estimated Install Time .25 hours	\$_____
6690640	<b>Wheel - 15 x 6 6ON5.5 +2.25.....</b> Works with Snow Tire pt#7425595 Estimated Install Time .25 hours	\$_____
6688856	<b>Wheel - 15 x 8 6ON5.5 +1.25.....</b> Works with Industrial Tires pt#'s7023288, 7023289 & Turf Tire pt#6682461 Estimated Install Time .25 hours	\$_____
6688857	<b>Wheel - 15 x 10 6ON5.5 +.25.....</b> Works with Turf Tire pt#7166360 Estimated Install Time .25 hours	\$_____
6690642	<b>Wheel - 16.5 x 9.75 6ON5.5 -.625.....</b> Works with Float Tire pt#7211382 Estimated Install Time .25 hours	\$_____